BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to Solid Waste Management in Ward No.07

Work Order No: EE (Project)/Ynk Zone/WO/ 15/2020-21 Dt:- 13/05/2020

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. U RAMESH	
				In figures	In words
1	12.00	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP , 50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: iCMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	24311.05	Rupees Twenty Four Thousand Three Hundred Eleven And Paise Five Only
2	4.00	Supplying, installation, Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	29916.45	Rupees Twenty Nine Thousand Nine Hundred Sixteen And Paise Forty Five Only
3	1.00	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	67443.23	Rupees Sixty Seven Thousand Four Hundred Forty Three And Paise Twenty Three Only
4	396.00	Providing and Fixing OFC cable single mode 6 core inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Mtr	173.20	Rupees One Hundred Seventy Three And Paise Twenty Only
5	4.00	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	23618.25	Rupees Twenty Three Thousand Six Hundred Eighteen And Paise Twenty Five Only
6	4.00	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	9972.15	Rupees Nine Thousand Nine Hundred Seventy Two And Paise Fifteen Only
7	4.00	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge	Nos	8922.45	Rupees Eight Thousand Nine Hundred Twenty Two And Paise Forty Five Only
8	4.00	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	6823.05	Rupees Six Thousand Eight Hundred Twenty Three And Paise Five Only
9	4.00	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	2309.34	Rupees Two Thousand Three Hundred Nine And Paise Thirty Four Only
10	4.00	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge	Nos	6718.08	Rupees Six Thousand Seven Hundred Eighteen And Paise Eight Only
11	4.00	Supplying ,installation ,Commissioning and Testing Patch cords CAT6 2 Mtr Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge	Nos	1574.55	Rupees One Thousand Five Hundred Seventy Four And Paise Fifty Five Only
12		GST @ 12%			

Executive Engineer
Project Division
Yelahanka Zone

Contractor